Keylargo Industrial Sdn. Bhd. (297660-M)
No. 73, Jalan Industri 2/5
Rawang Integrated Industrial Park, 48000
Rawang, Selangor Darul Ehsan, Malaysia
Tel : +60 (3) 6094 2099
Fax : +60 (3) 6094 2033
email : keylargo@keylargo.com.my

To : -
Attn : -
Tel : -
Mobile : -
Email : -

Original Date : Monday, 26 October 2026

Quotation

Project : -
Your reference : -
Our reference : RC-2610-0238
Handled by : -

Dear Sir / Madam,

We like to thank you for your inquiry and pleased to submit our quotation on the terms set out below.

Delivery : Ex - Stock subject to prior sales. Otherwise 2-3 months upon confirmation order.
Term : Cash before delivery
Validity : 14 days
Price Basis : Ex - K.L. only, nett in Ringgit Malaysia.

Please contact us if you have any remaining question(s) or when this quotation is not in line with your requirements.

We would appreciate to receive feedback and to keep us informed about the status of this quotation.

Your sincerely,

Keylargo Industrial Sdn. Bhd.

Date: **Monday, 26 October 2026**
Our Reference: **RC-2610-0238**

Pos.		Qty	Unit Price	Total
1	**KeyPLC VSD Booster System (2Pumps System)** Vertical Multistage Pump Model: CHC 32-20 c/w 5.5HP 2Pole IE3 Motor (415V / 3Ph / 50Hz) Suction & Discharge: DN65 x DN65 Material: SS304 (Cast Iron Connection) / Mechanical Seal c/w KeyPLC Control Panel (Sheltered) Pump Controller & HMI Touch Screen @ 1 Lot 4kW VFD @ 2 nos & Pressure Transmitter @ 1 no Wiring for pumps & pressure transmitter within pump skid @ 1 Lot c/w Baseplate in mild steel, GI manifold 4" inlet & 4" outlet Gate valves on the suction and discharge ports of each pump Check valve on the discharge port of each pump 1 pressure gauge on the discharge manifold c/w 100 litres (10 bar) non-jkkp approved tank @ 1 unit	1 Set	27,240.00	27,240.00
2	**KeyPLC VSD Booster System (2Pumps System)** Vertical Multistage Pump Model: CHC 4-30 c/w 0.75HP 2Pole IE3 Motor (415V / 3Ph / 50Hz) Suction & Discharge: DN32 x DN32 Material: SS304 (Cast Iron Connection) / Mechanical Seal c/w KeyPLC Control Panel (Sheltered) Pump Controller & HMI Touch Screen @ 1 Lot 0.75kW VFD (1Ph In / Ph Out) @ 2 nos & Pressure Transmitter @ 1 no Wiring for pumps & pressure transmitter within pump skid @ 1 Lot c/w Baseplate in mild steel, GI manifold 2" inlet & 2" outlet Gate valves on the suction and discharge ports of each pump Check valve on the discharge port of each pump 1 pressure gauge on the discharge manifold c/w 24 litres (10 bar) non-jkkp approved tank @ 1 unit	2 Sets	15,150.00	30,300.00

E & O.E.

Date: **Monday, 26 October 2026**
Our Reference: **RC-2610-0238**

Pos.		Qty	Unit Price	Total
3	**KeyPLC VSD Booster System (2Pumps System)** Vertical Multistage Pump Model: CHC 10-30 c/w 1.5HP 2Pole IE3 Motor (415V / 3Ph / 50Hz) Suction & Discharge: DN40 x DN40 Material: SS304 (Cast Iron Connection) / Mechanical Seal c/w KeyPLC Control Panel (Sheltered) Pump Controller & HMI Touch Screen @ 1 Lot 1.5kW VFD (1Ph In / Ph Out) @ 2 nos & Pressure Transmitter @ 1 no Wiring for pumps & pressure transmitter within pump skid @ 1 Lot c/w Baseplate in mild steel, GI manifold 2.5" inlet & 2.5" outlet Gate valves on the suction and discharge ports of each pump Check valve on the discharge port of each pump 1 pressure gauge on the discharge manifold c/w 24 litres (10 bar) non-jkkp approved tank @ 1 unit	1 Set	17,170.00	17,170.00
4	**KeyPLC VSD Booster System (2Pumps System)** Vertical Multistage Pump Model: CHC 10-30 c/w 1.5HP 2Pole IE3 Motor (415V / 3Ph / 50Hz) Suction & Discharge: DN40 x DN40 Material: SS304 (Cast Iron Connection) / Mechanical Seal c/w KeyPLC Control Panel (Sheltered) Pump Controller & HMI Touch Screen @ 1 Lot 1.5kW VFD (1Ph In / Ph Out) @ 2 nos & Pressure Transmitter @ 1 no Wiring for pumps & pressure transmitter within pump skid @ 1 Lot c/w Baseplate in mild steel, GI manifold 2.5" inlet & 2.5" outlet Gate valves on the suction and discharge ports of each pump Check valve on the discharge port of each pump 1 pressure gauge on the discharge manifold c/w 24 litres (10 bar) non-jkkp approved tank @ 1 unit	4 Sets	17,170.00	68,680.00

Sub-total		**143,390.00**
0% SST		**0.00**
Total		**143,390.00**

E & O.E.